

Dragline Relocations using Self Propelled Modular Transports (SPMTs)

May 19th , 2015

Prepared for 2015 Haulage & Loading Conference

Dragline Relocations using SPMT – BE 1350

1350 Transport Scope:

 One BE 1350 Dragline and shoes at Big Brown Mine

Weight approx. 5.5M lbs

Transport distance approx. 3.3 miles

Used 120 axle lines of SPMTs

approx. 10 days to mobilize & load

approx. 2 days to transport

approx. 4 days to unload & demobilize

Obstructions etc.

345 KV High Voltage OH Line 150 ft concrete box culvert low water bridge Multi-plate superspan bridge 3 OH distribution lines (internal to LUM)



Dragline Relocations using SPMT – BE 1570

1570 Transport Scope:

•

One BE 1570 Dragline and shoes at Kosse Mine Weight approx. 7.5M lbs **Transport distance approx. 6.7 miles** Used 150 axle lines of SPMTs approx. 7 days to mobilize & load approx. 3.5 days to transport approx. 3 days to unload & demob **Obstructions etc.** 345 KV High Voltage OH Line State Hwy 7 (at grade) **2 OH distribution lines** misc internal CMPs



Dragline Relocations using SPMT – Marion 8750W

8750 Transport Scope:

• Two Marion 8750W Draglines at Martin Lake Beckville Mine . 4 Shoes, 2 Elect. Subs w/Switch

Weight approx. 13M lbs each Used 240 axle lines of SPMTs <u>Delta 33 move:</u> approx. 15 miles

11 dys to mobilize & load

15 dys to transport

4 dys to unload & demob to D32

Delta 32 move:

approx. 8 miles

3 dys to mobilize & load

4 dys to transport

6 dys to unload & demob

Obstructions etc.

35 nat gas pipelines,12 OH Power L

4 railroad crossings, 7 CR and FM crossings





Luminant Video



SIZE MATTERS

1 BE1350 (5.5M lbs)

1 BE1570 (7.5M lbs)







1 M8750 (13M lbs)

Engineering for Loading and Jacking



Engineering for Loading and Jacking



LOADING Step 1 & 2 - POSITION JACKS & TEST LIFT



Right side of Machine (Ready to take full load overnight)

Front of Machine

LOADING Step 3 - FULL LIFT



(Ready for Positioning SPMTs)

Front of Machine

LOADING Step 4 – INITIAL POSITION SPMTs



Right side of Machine (Center SPMTs positioned)



Front of Machine

LOADING: Steps 5 thru 7 – COMPLETE LOADING SEQUENCE



Front of Machine

Front of Machine (Last Jacks Ready for Removal)

Front of Machine (Ready for Transport)

Loading Animation video

Luminant Kosse Dragline 002.mp3

BE 1350-W





BE 1570-W







M 8750 W







BE 1350-W

BE 1570-W M 8750 W



















BE 1570-W M 8750 W









<u>"Opportunities":</u>















Yes... more Opportunities...

















Liberty Bridge Video

D32 Liberty Bridge xing.mp3



SUMMARY – Lessons Learned & Pros

Lessons Learned :

• Loading and unloading pad areas require much more area – more equipment staging are than expected (20 loads per day for 3 days). Mob & Demob \$'s are significant

- Walkway subgrade and surface prep is extremely important !
- Removal of Bucket and Ropes /keep the ropes on & "link" them together adjust CG Calculations
- Removal of Tub Growsers are critical path critical for load distribution , remove and reinstall on backshifts
- Support required Diesel fuel supply, Water trucks, fork trucks, flat tires and lots of 8'x 15' x 3/16" steel plate

Pros:

- Much less dirt work \$s for Dragline walkway construction narrower for SPMT transport (even less \$s if reclamation is required)
- Engineered jacking method is fast and safe!
- Haulroad is not destroyed
- No wear and tear on propel gearing for deadhead on longer moves
- No Trail cable issues to mess with during move cable is removed and then reinstalled
- Faster & Approx. 2/3 cost of walking ... or less... depending on distance and "opportunities" etc.

Job done safely... Job done well... THE END!!



Questions?